

**Addendum Number Four**

To the Drawings and Specifications for:

**USD 358 – OXFORD JR/SR HIGH SCHOOL ADDITION**

Issued: February 4, 2020

**HANNEY & ASSOCIATES ARCHITECTS**

1726 South Hillside, Wichita, Kansas

**NOTICE TO BIDDERS**

You are hereby instructed to include in your bids the following changes, clarification and/or corrections to the Drawings and Specifications for the **Oxford USD 358 Jr/Sr High School Addition**.

The additions and/or corrections shall be considered as a part of the Contract Documents as if incorporated therein. Where the following corrections and/or additions vary from the conditions of the Drawings and Specifications, such following changes or additions shall govern.

**1. GENERAL CLARIFICATIONS**

- 1.1 The Bid Date shall remain **Friday, February 7, 2020**. The time and location to receive the bids remains unchanged.

**2. CHANGES TO SPECIFICATIONS**

- 2.1 Section 09700 “Resinous Flooring”, Paragraph 4, “Flooring Material”, Section 4.1, **Tnemec shall be an approved equal.**
- 2.2 Section 15400 - Plumbing Fixtures 15400 1.02 Acceptable Manufacturers:
  - a. “C” - Lavatory System - Bradley Express Lav System and Faucets is an approved equal.
  - b. “E” - Flush Valves – Zurn is an approved equal.
  - c. “J” – Showers – Bradley Showers is an approved equal.

**3. CHANGES TO ELECTRICAL DRAWINGS – REVISED SHEETS**

- 3.1 Sheet E2.3:

Contractor shall provide surface mounted card reader (refer to architectural plans for card reader location) and conduit as required for access controls associated with door #500b. Contractor shall also provide 120V input to electric strike power supply located above ceiling. Contractor to connect 120V circuit to nearest 120V receptacle circuit in area. Coordinate exact requirements with door hardware provider.

3.2 Sheet E2.4

Contractor shall provide recessed mounted card reader (refer to architectural plans for card reader location) and conduit as required for access controls associated with the following doors:

- a. 211a.
- b. 212a
- c. 300b
- d. 318a

Contractor shall also provide 120V input to electric strike power supply located above ceiling. Contractor to connect 120V circuit to nearest 120V receptacle circuit in area. Coordinate exact requirements with door hardware provider.

**END OF ADDENDUM FOUR**