

Addendum Number TWO

To the Drawings and Specifications for:

USD 358 – OXFORD JR/SR HIGH SCHOOL

Issued: January 22, 2020

HANNEY & ASSOCIATES ARCHITECTS

1726 South Hillside, Wichita, Kansas

NOTICE TO BIDDERS

You are hereby instructed to include in your bids the following changes, clarification and/or corrections to the Drawings and Specifications for the **Oxford USD 358 Jr/Sr High School Addition**.

The additions and/or corrections shall be considered as a part of the Contract Documents as if incorporated therein. Where the following corrections and/or additions vary from the conditions of the Drawings and Specifications, such following changes or additions shall govern.

1. GENERAL CLARIFICATIONS

- 1.1 A non-mandatory site visit, walk-thru, has been scheduled for Monday, January 27, 2020, **at 10 o'clock a.m.**, Oxford Jr/Sr High School, 515 N. Water Street, Oxford, Kansas, 67119

2. CHANGES TO SPECIFICATIONS

- 2.1 Section 09650 “Resilient Floor Covering”, Paragraph 2, “Work Included”, shall be changed to read: **The floor covering installer shall furnish all labor and materials to complete all work in connection with floor finishes required by the drawings and/or herein specified as follows.**
- 2.2 Section 09650 “Resilient Floor Covering”, Paragraph 4, “Materials”, Section 4.2, “Rubber Base”, letter A shall read: **The floor covering installer shall provide and install rubber base on walls where called for by the Room Finish Schedule for the entire project. Material shall be from roll stock in lieu of pre-cut 4’ lengths. No pieces less than 24” shall be installed. Inside and outside corners shall be field formed.**
- 2.3 Section 09650 “Resilient Floor Covering”, Paragraph 4, “Materials”, Section 4.3, “Rubber Transition Strips/Reducer Strips”, letter A shall read: **The floor covering installer shall provide and install rubber transition strips where flooring meets another flooring type (rubber, LVT and the carpeting).**
- 2.4 Section 09650 “Resilient Floor Covering”, Paragraph 4, “Materials”, Section 4.3, “Rubber Transition Strips/Reducer Strips”, letter B shall read: **The floor covering**

installer shall provide and install rubber reducer strip or edge reducer strip where new flooring material meets existing VCT.

3. REVISION TO INDEX

3.1 Sheet MP2.1 should be removed from the Index. There is no sheet issued as MP2.1.

4. FINISHES SCHEDULE

4.1 Sheet A8.1, Corridor 300, floor finish is sealed concrete with new rubber base.

END OF ADDENDUM TWO