

MATERIAL GENERAL NOTES	
INTERIORS	
ID #	GENERAL NOTE
G.N. (INT) #1	ALL WORK IS TO BE IN ACCORDANCE WITH OXFORD, KS BUILDING CODES AND ALL OTHER CODES WHICH MAY HAVE AUTHORITY OVER THIS PROJECT. PROVIDE ALL NECESSARY SAFEGUARDS, BARRIERS, TEMPORARY POWER, LIGHTING, FIRE PROTECTION, ETC AS REQUIRED DURING CONSTRUCTION.
#2	G.C. TO PROVIDE AND INSTALL MATERIALS PER MANUFACTURER'S RECOMMENDATION. PROVIDE ACCESSORIES, TRIM COMPONENTS, ETC REQUIRED FOR COMPLETE INSTALLATION OF SPECIFIED MATERIAL.
#3	REFER TO PLANS, ELEVATIONS, SECTIONS AND SPECIFICATIONS FOR ADDITIONAL MATERIALS, EXTENT OF FINISH AND ADDITIONAL INFO. CONFLICTING NOTES TO BE BROUGHT TO ARCHITECT FOR REVIEW AND FINAL DECISION. PATCH AND REPAIR NOTATION MEANS NEWLY INSTALLED MATLS SHALL MATCH MATL AND COLOR OF EXIST'G MATLS UNLESS NOTED OTHERWISE.
#4	FLOOR, WALL, CEILING: OPEN AREAS BENEATH/BEHIND EQUIPMENT, CABINETRY, AND MILLWORK, INSTALLER TO EXTEND NEW FINISH TO COVER OPEN AREA (APPLIES TO VIEWABLE AREAS ONLY, UNLESS NOTED OTHERWISE.)
#5	COLORS NOTED ARE FOR BIDDING PURPOSES ONLY. FINAL COLOR SELECTIONS BY ARCHITECT PRIOR TO ORDERING MATERIALS.
#6	ALL FINISHES PRODUCING NOXIOUS OR IRRITATING FUMES OR ODORS (ELECTROSTATIC PAINTING, FLOOR FINISHING, ETC) SHALL BE DONE ONLY AFTER BUILDING MANAGEMENT REVIEW AND ONLY AFTER BUSINESS HOURS.
#7	PROVIDE A SUBMITTAL SCHEDULE ALLOWING FOR LONG LEAD TIME ITEMS TO PREVENT SUBSTITUTIONS.
#8	INTERIOR WALL AND CEILING FINISH: EXIT- CLASS A, CORRIDORS- CLASS A, ROOMS AND ENCLOSED SPACES- CLASS A. FLOOR FINISH: EXIT- NOT LESS THAN CLASS II IN ACCORDANCE WITH NFPA 253, SHALL COMPLY WITH DOC FF-1, "FILL TEST" (CPSC 16 CFR, PART 1630). FINISHES SHALL COMPLY WITH OR EXCEED THE CURRENT BUILDING CODE MINIMUM REQUIREMENTS.SMOKE DENSITY OF FINISH MATLS: LESS THAN 450. INTERIOR FLOOR FINISHES SHALL MEET ALL REQUIREMENTS OF SECTION 804 IBC. SEE TABLE 803.5 FOR FOOTNOTES.

FLOORING	
ID #	GENERAL NOTE
G.N. (FLR) #1	PROVIDE SHOP DRAWINGS LAYOUT SHOWING ALL FLOOR PATTERN LOCATIONS, GRAIN DIRECTION AND SEAMING DIAGRAMS. CONDUCT MOISTURE TESTS ON ALL CONCRETE SLABS WHERE FINISH MATERIALS ARE SCHEDULED. RECORD PASSING MOISTURE LEVELS PRIOR TO START OF INSTALLATION. REFERENCE MANUFACTURERS INSTALLATION SPECIFICATIONS FOR EACH FLOOR FINISH TYPE TO VERIFY AND PROVIDE REMEDY TO MATCH MOISTURE LEVEL REQUIREMENTS.
#2	FLOORING CONTRACTOR: TILEWORK SHALL HAVE EXPANSION JOINT AT PERIMETER WALL/FLOOR JOINT. INFILL WITH A SEALANT.
#3	ALL VCT, CORK/RUBBER, AND OTHER HARD SURFACE FLOORING TO BE PREP'ED AND SEALED PER MANUF'S RECOMMENDATIONS
#4	ALIGN TRANSITION OF FLOOR MATERIAL WITH CENTER OF HINGE IN DOORWAY. PROVIDE TRANSITION AS INDICATED BELOW: VCT TO CARPET: TR#1 VCT TO CONCRETE: TR#2
#5	REMOVE EXISTING FLOORING, ADHESIVE AND MASTIC AT ALL EXISTING FLOORING SCHEDULED FOR DEMOLITION. PATCH AND PREP SUBFLOOR TO MEET MANUFACTURER'S REQUIREMENTS FOR NEW FLOORING MATERIALS. FLOAT SUBFLOOR AS NECESSARY TO ACHIEVE A SMOOTH & LEVEL FLOORING SURFACE.

BASE	
ID #	GENERAL NOTE
G.N. (BASE) #1	RUBBER COVE BASE ON ALL BUILT-IN BASE CABINETS, EXPOSED STRUCT COLUMNS, ETC. G.C. TO PROVIDE AND INSTALL CABINET BASE. FRAMEWORK HEIGHT SHALL BE 4" HEIGHT. COORDINATE LENGTH AND WIDTH WITH MILLWORK CONTRACTOR.
#2	WHERE SPECIFIED PROVIDE CONTINUOUS LENGTH OF RUBBER BASE WITH FIELD FORMED CORNERS.

WALL	
ID #	GENERAL NOTE
G.N. (WALL)#1	COORDINATE PRE-INSTALLATION MEETING FOR PATTERNED WALL TILE. PROVIDE SHOP DRAWINGS TO CONFIRM TILE LAYOUT BEFORE INSTALLATION.
#2	PATCH AND PREP ALL EXISTING WALLS TO REMAIN FOLLOWING DEMO. CONFIRM EQUIPMENT MOUNTING HEIGHTS WITH OWNER PRIOR TO RE-INSTALL.
#3	PROVIDE CERAMIC/PORCELAIN TILE TRIM PIECES - BULLNOSE, INSIDE/ OUTSIDE CORNERS, ETC. METAL TRIM PIECE WHERE NOTED
#4	ALL EXISTING DOORS REMAINING TO REMAIN UNTOUCHED UNLESS NOTED OTHERWISE.
#5	INTERIOR H.M. FRAMES AND DOORS: PAINT. COLOR VARIES. EXTERIOR H.M. DOORS AND FRAMES: PAINT. COLOR VARIES. PAINT COLORS TO BE SELECTED ON SHOP DRAWINGS BY ARCHITECT.
#6	G.C. TO PAINT EXPOSED SIDE OF G.N.B. AT NEW CONSTRUCTION, UNLESS OTHERWISE NOTED. PROVIDE A SMOOTH LEVEL 4 DRYWALL FINISH ON ALL GYPSUM WALLS AND CEILING OTHERWISE NOTED. LEVEL 4 IS PER CURRENT VERSION OF RECOMMENDED LEVELS OF GYPSUM BOARD FINISH ACCESSSED ON THE GYPSUM ASSOCIATION WEBSITE. 6A-214-15
#7	GENERAL CONTRACTOR AND WALL FINISH CONTRACTOR SHALL COORDINATE INSTALL OF FINISH MATERIALS. G.C. SHALL INSURE THE SURFACE CONDITION WILL NOT ADVERSELY AFFECT THE INSTALLATION OF THE WALL FINISH.
#8	ALL ELECTRICAL DEVICES LOCATED WITHIN AREAS SCHEDULED TO RECEIVE NEW FINISHES, NEW AND EXISTING: PROVIDE NEW COVER PLATES. VERIFY FINISH COLOR WITH ARCHITECT.
#9	PAINTED WALLS: CONFIRM COLOR WITH ARCHITECT AND OWNER PRIOR TO COMMENCING. PAINT SHEENS: REFER TO MANUFACTURER'S STANDARD DEFINITION FOR GLOSS RANGE ON THE FOLLOWING PAINT SHEENS: SATIN. PAINTED WALLS RECEIVE A TINTED PRIMER THAT COORDINATES WITH FINISH COLOR. ALL PAINTED GYPBD. TO BE SATIN FINISH. ALL CMU TO BE SEMI-GLOSS FINISH.
#10	PAINTED WALLS RECEIVE A TINTED PRIMER THAT COORDINATES WITH FINISH COLOR.
#11	WALL SURFACES TO BE PROPERLY PREPARED WITH RELEASE PRIMER PRIOR TO INSTALLATION OF WALLCOVERINGS.


CEILING	
ID #	GENERAL NOTE
G.N. (CLG)#1	CENTER CEILING GRID AND TILE LAYOUT IN EACH ROOM UNLESS OTHERWISE NOTED. DO NOT INSTALL LESS THAN 1/2" CLG TILE.
#2	REFER TO REFLECTED CEILING PLANS AND A2.4 FOR ADDITIONAL SOFFIT AND CEILING DETAILS.

MISCELLANEOUS	
ID #	GENERAL NOTE
G.N. (MISC)#1	PROVIDE BLOCKING AT ALL WALLS SCHEDULED FOR WALL HUNG EQUIPMENT. ALL FURNITURE IS OWNER FURNISHED AND GENERAL CONTRACTOR INSTALLED UNLESS OTHERWISE NOTED.
#2	ROOM SIGNS ARE PROVIDED BY & INSTALLED BY GENERAL CONTRACTOR UNLESS OTHERWISE NOTED.
#3	G.C. SHALL INSTALL SIGNAGE AT INTERIOR OPENINGS TO HALLS, CORRIDORS OR EXTERIOR EXITS WHERE SIGNAGE IS SCHEDULED FOR ROOM. ALL SIGNAGE SHALL BE IN ACCORDANCE TO CURRENT LOCAL AND STATE REGULATIONS.
#4	PUBLIC AREAS AND NEW CLASSROOMS: WALLS WITH EXTERNAL CORNERS SHALL RECEIVE CORNER GUARDS.
#5	PAINT GRILLS, WALL DIFFUSERS, ELECTRICAL PANELS, WALL MOUNTED BOXES, ACCESS PANELS, ETC., WHICH ARE EXPOSED IN FINISHED SPACES TO MATCH THE SURFACE ON WHICH THEY OCCUR.
#6	CLEAN JOB SITE, REMOVING SCRAPS, DEBRIS AND WASTE MATERIALS DAILY.


FINISH MATERIAL LEGEND													
FLOOR MATERIAL										SETTING MATERIALS , UNDERLAYMENTS, MEMBRANE, SEALERS			
ID #	MATERIAL	MANUFACTURER	PRODUCT	COLOR	DIMENSION	SETTING	TRIM	ADDL INFORMATION		ID #	MANUFACTURER	PRODUCT	ADDITIONAL INFO
F1	SEALED CONCRETE	SEAL-KRETE	DURA-SHELL WB	CLEAR W/ N.S. ADD.	(FULL COVERAGE)	2 COATS				SM-1	ARMSTRONG	QUIET COMFORT	S-1841, 6' x 16.7' x 0.17" THK, FULL COVERAGE
F2	CARPET-MODULAR	J+J INDUSTRIES	INTRINSIC 7096	2720 FUNDAMENTAL	24"x24"	SM-2			MANUFACTURE'S RECOMMENDED	SM-1	ADHESIVE	FINISH MATERIAL MANUF	MANUF'S RECOMMENDED, FULL COVERAGE
F2A	CARPET-MODULAR *ALTERNATE	MILLIKEN	JOURNAL/INSCRIPTION	INS154 w/ PUNCH/CARBON	19.7"x19.7" (50cm x 50cm)	SM-2			PROVIDE ALTERNATE BID FOR CARPET F2A	SM-1	TILE AND GROUTS	FINISH MATERIAL MANUF	MANUF'S RECOMM. PROTECTION & SEALERS
F3	NOT USED												
F4	VCT	ARMSTRONG	PR.EX.CROWN TEXTURE	COLOR 1	12"x12"	SM-1							
F5	VCT	ARMSTRONG	PR.EX.CROWN TEXTURE	COLOR 2	12"x12"	SM-1							
F6	VCT	ARMSTRONG	PR.EX.CROWN TEXTURE	COLOR 3	12"x12"	SM-1							
F7	CARPET-MODULAR WALK-OFF	J+J INDUSTRIES	RUNWAY (7000m) 1419	VIP PASS	24"x24"	SM-2							
STAIR FLOORING MATERIAL										GROUT AND MAINTENANCE			
ID #	MATERIAL	MANUFACTURER	PRODUCT	COLOR	DIMENSION	SETTING	MTL TRIM	ADDL INFORMATION		ID #	MANUFACTURER	PRODUCT	COLOR
F7	RAISED CIRC RUBBER TREAD	ROPPE	RUBBER TREAD	100 BLACK	12" D x 108" L, #99	SM-2	-	NOSING ADHESIVE; EPOXY NOSE FILLER		G-1	BOSTIC	EZ-POXY	
F8	PAINTED RISER	SHERWIN WILLIAM	PRO-CRY UNIV PRIM/ PRO	INKWELL SW6992	5.2 DRY MILLS TOTAL	-	-			G-2	BOSTIC	EZ-POXY	
F9	PAINTED STRINGER	SHERWIN WILLIAM	IND ACRYLIC LOW SHEEN	DORIAN SW7017	5.2 DRY MILLS TOTAL	-	-			G-3	BOSTIC	TRU COLOR	
										G-4	BOSTIC	TRU COLOR	
										G-5	BOSTIC	SANDED	
										SM-7	FINISH MATERIAL MANUF	MANUF'S RECOMM. INITIAL MAINTENANCE FINISH APPLICATIONS.	
WALL BASE MATERIAL										TRIMS			
ID #	MATERIAL	MANUFACTURER	PRODUCT	COLOR	DIMENSION	SETTING	MTL TRIM	ADDL INFORMATION		ID #	MANUFACTURER	PRODUCT	COLOR
B1	RUBBER WALL BASE	ROPPE	PINNACLE, STAND, COVE	193 BLACK BROWN	4" X 1/8"	SM-2	-	-		T-1	ROPPE	#74 ROLLING TRAFFIC	193 BLACK BROWN
										T-2	ROPPE	TILE/CARPET JOINER	193 BLACK BROWN
										T-6	ROPPE ACCESSORIES	STAIR NOSING: 2"	BLACK
										T-3	SCHLUTER	RENO-UJ	NOT USED
										T-4	SCHLUTER	RONDEC	NOT USED
										T-5	SCHLUTER	TREP-B 2-1/8"	NOT USED
										T-10	SCHLUTER	RONDEC-STEP	NOT USED
										T-12	SCHLUTER	QUADEC	NOT USED
								NOTE: SPECIAL COLORS REQUIRE 10 WEEK LEAD TIME		INCL. ADDTL. ACCESSORIES FOR COMPLETE INSTALL: FOR EXAMPLE, BUT NOT LIMITED TO END CAPS ON EXP EDGES			
CEILING FINISH MATERIALS										DOOR STAIN, AND WOOD TRIM:			
ID #	MATERIAL	MANUFACTURER	PRODUCT	COLOR	DIMENSION	SETTING	MTL TRIM	ADDL INFORMATION		ID #	MANUFACTURER	PRODUCT	COLOR
C1	ACOUSTICAL TILE	ROCKFON, CLASS A	ARTIC: STONE WOOL	WHITE	24" x 24" x 5/8"	SQ EDGE	-	C1A; 24 X 48, NRC: .75		ST-1	SHERWIN WILLIAMS	STAIN COLOR	CUSTOM MATCH TO MATCH EXISTING
	15/16 SUSPENSION SYSTEM	CHICAGO METALLIC	FIRE RATED: 1 HR	WHITE	24" x 24" SYSTEM	-	-						
C2	ACOUSTICAL TILE	ROCKFON, CLASS A	ALASKA: STONE WOOL	WHITE	24" X 24" x 3/4"	SQ EDGE	-	NRC: .90					
	15/16 SUSPENSION SYSTEM	CHICAGO METALLIC	FIRE RATED: 1 HR	WHITE	24" x 24" SYSTEM	-	-						
SPECIAL PROVISIONS REQUIRED: ALL WOOD AND WOOD LOOK MATERIALS SHALL MATCH EXISTING WOOD													

ELEMENTARY SCHOOL ROOM FINISH SCHEDULE


FIRST FLOOR ROOM NAME	ROOM #	FLOOR DTL/SH	BASE DTL/SH	WALLS: DTL/SH				CEILING		MILLWORK	WINDOW SILL	FINISH NOTE
				NORTH	SOUTH	WEST	EAST	MAT'L	HEIGHT			
SECURE ENTRY	100	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	-	M1	-	
CHECK IN	101	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	-	M1	-	
RECEPTION	102	EXISTING	B1	W2	W2		W2	EXISTING	WATCH EXISTING	M1		REF. A2.3, REFL. CLG. PLANS
PRINCIPAL	104	EXISTING	B1	W2	W2	W2	W2	EXISTING	WATCH EXISTING			
MULTIPURPOSE	110	-	(SEE NOTE)	EXISTING			EXISTING	EXISTING	WATCH EXISTING			NEW BASE AT NEW INFILL WALL
STAGE	111	EXISTING	EXISTING	W2	W2	W2	W2	EXISTING	-			
STORAGE	112	EXISTING	B1	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	-			
CORRIDOR	130	F4, F5	B1	W2, W4	W2, W4	W2, W4	W2	C3	10'-0"			REF. INTERIOR ELEVATIONS A6.3
STORAGE	128	EXISTING	B1	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	-			
CLASSROOM	132	F2/F2A, F4, F6	B1	W2	W2	W2	W2	C1	9'-0"	M2		REF. ELEV.S AND DETAILS FOR TILE PATTERN
CLASSROOM	133	F2/F2A, F4, F6	B1	W2	W2	W2	W2	C1	9'-0"	M2		REF. ELEV.S AND DETAILS FOR TILE PATTERN
TOILET ROOM	134	F4/F6	B1	W2/W4	W2/W4	W2/W4	W2/W4	C2	9'-0"	M3		REF. TO ENLARGED PLAN FOR FOR FIN. LOCATIONS
CORRIDOR	150	F4/F5	B1	W2/W4	W2/W4	W2/W4	W2/W4	C3	10'-0"			REF. TO ENLARGED PLAN FOR FOR FIN. LOCATIONS
VESTIBULE	151	F7	B1	W2	W2	W2	W2	C3	10'-0"			
TOILET ROOM	152	F4/F6	B1	W2/W4	W2/W4	W2/W4	W2/W4	C2	8'-0"	M3		REF. ELEV.S AND DETAILS FOR TILE PATTERN
CORRIDOR	153	F4, F5	B1	W2	W2	W2	W2	C3	10'-0"			REF. ELEV.S AND DETAILS FOR TILE PATTERN
TOILET ROOM	154	F4/F6	B1	W2/W4	W2/W4	W2/W4	W2/W4	C2	8'-0"	M3		REF. ELEV.S AND DETAILS FOR TILE PATTERN
STORAGE	156	F6	B1	W2	W2	W2	W2	C5	10'-0"			
CORRIDOR	160	F4, F5	B1	W2/W4	W2/W4	W2/W4	W2/W4	C3, C4	9'-0"			REF. ELEV.S AND DETAILS FOR TILE PATTERN VCT AT STAIR LANDING
CLASSROOM	161	F2/F2A, F4, F6	B1	W2	W2	W2	W2	C1	9'-0"	M2		
MEDIA CENTER	162	F2/F2A	B1	W2	W2	W2	W2	C3	10'-0"	M1		RUBBER TREADS AT STAIRS, CARPET AT LANDING BACKSPLASH, W4, COLOR: MATTE BISCUIT K775
CLASSROOM	163	F2/F2A, F4, F6	B1	W2	W2	W2	W2	C1	9'-0"	M2		
VESTIBULE	164	F7	B1	W2	W2	W2	W2	C3	10'-0"	M2		




ORDER'G: INCL (1) ADD'L BOX(S) OF EA ACCENT COLOR, (2) BOX(S) OF FIELD COLOR
TILE WAINSCOT / TOILET ROOMS
CONCEAL ATTACHMENT OF MIRROR
REFER TO SPEC SECTION 08800 FOR GLAZING TYPE INFORMATION



ORDER'G: INCL (1) ADD'L BOX(S) OF EA ACCENT COLOR, (2) BOX(S) OF FIELD COLOR
CORRIDOR TILE WAINSCOT



3 RUBBER FLOOR TILE STAIRS
FIELD VERIFY NOSING PROFILE
STAIR TREAD PRODUCT PROFILE TO ACCOM. CONDITIONS



9/12/19

HANNEY & ASSOCIATES, ARCHITECTS
1726 South Hillside, Wichita, Kansas, 67211
Phone (316) 683-8965
Fax (316) 684-1441
www.hoarchitects.com